



Public Information Meeting For Northview Road Phase 2 and Meadowbrook Park Improvements



Purpose of the Improvement

- Full roadway reconstruction of Northview Rd from 250' east of Meadowbrook Road to 150' west of Tallgrass Circle.
- Installation of new storm sewer and culverts, and installation and/or adjustment of storm sewer catch basins;
- Removal of existing drive approaches and replacement of drive approaches with 6-Inch or 7-Inch concrete pavement;
- Installation of updated curb ramps, sidewalk and/or grading for future sidewalk;
- Installation of pavement markings and permanent signing;
- Construction of Meadowview Park site grading, preparation for future path system, and asphalt parking lot.

Proposed Major Changes

- The roadway cross section will consist of a mix of both rural sections (with ditching) and urban sections (with concrete curb and gutter).
 - The rural sections will include one 11' wide travel lane and 6' outside shoulder in each direction.
 - The urban sections will include one 11' wide travel lane and 5' outside shoulder with 30" curb and gutter in each direction.
- Addition of a 5' – 6' paved shoulder along both sides of Northview Rd.
 - There will be No Parking along Northview Rd.
- Some trees within the existing roadway right-of-way will need to be removed for the new roadway grading.
- Addition of City street lighting at intersections.

Sidewalks

- There have been no changes/updates since the Board of Public Works Meeting on February 22, 2018.
- Sidewalks will not be installed along properties residing within the BAA with this reconstruction project, however, the grading adjacent to the new roadway would not preclude a sidewalk in the future.
- Sidewalks will be installed along properties within the full reconstruction limits outside of the BAA.

Important Dates

- Common Council Award Date – January 15, 2019. Recommended award to Super Western, Inc. for low bid of \$2,705,754.95
- Anticipated Reconstruction Project Start – Mid-March 2019
- Completion of Northview Rd. Phase 2 Reconstruction and Meadowview Park Improvements – August 3, 2019
 - The contract includes an interim completion date for Northview Rd. to re-open prior to July 2, 2019.

Traffic Control/Access

- During construction, Northview Rd. will be closed to through traffic.
- Access to driveways within the work zone will be maintained as much as possible.
- During paving operations, direct access to driveways will be restricted, however, overnight parking will be allowed/coordinated within the work zone and on adjacent side streets.
- Garbage and Recycling pick-up will continue on the regular day/schedule.
- Mail services will be maintained through construction. The contractor will coordinate relocation of existing mailboxes.

Project Contact

If you have any questions, comments or would like additional information please contact:

Brandon Schwenn, P.E.
City of Waukesha Project Manager
262-524-3585
bschwenn@waukesha-wi.gov.

To receive updates on closures and project activities, please send your e-mail address to bschwenn@waukesha-wi.gov. Updates will be sent weekly or if conditions change. Updates will also be placed onto the City's Website: <http://www.waukesha-wi.gov/1136/Current-Construction-Projects>